



BID NO.: 11-009

**FIRE STATION NO. 2 PHASE 2B INTERIOR REHABILITATION AND
PARKING LOT**

New Bid Submission Date: December 16th, 2011

Due Time: 2:00 P.M.

**Addendum #3
December 12th, 2011**

Pieter A. Bockweg, CRA Executive Director

ISSUED BY

City of Miami Community Redevelopment Agency
49 NW 5th Street, Suite 100
Miami, Florida 33128

CONTACT

Phone: 305-679-6800
Fax: 305-679-6835
Attention: Mark Spanioli, P.E.
Director of Engineering and Construction
Email: mspan@miamigov.com



This addendum is being issued as clarification to the Invitation to Bid # 11-009 issued on November 9th, 2011. This addendum should be considered a supplement to the original ITB that shall provide clarifications to the questions posed during the additional information and clarification period.

Questions posed during the clarification period with responses related to the interior build-out:

RFI from JRT Construction:

1. Plumbing Spec section 15420 states NO HUB CAST IRON above grade and EXTRA HEAVY WEIGHT BELL & SPIGOT CAST IRON below grade. Note on Page P1.00 states Sanitary Waste & Vents to be PVC. Please advise which document governs? **Answer: Use PVC**
2. Plumbing Spec section 15440 calls for Wall Hung water closets. Plumbing floor plans and Architectural elevations indicate Floor Mount water closets. Please advise which will be required? **Answer: Floor Mounted**